

Sub: “Corrigendum” to the Specification of Construction of toilet at Kohinoor Mills No. 1 & 2.

We, vide our letter no. NTC(WR)/AM/2017/142 dated May 17, 2017 have given the specification for the construction of toilet at Kohinoor Mills 1 & 2. There is one correction in the specification which is to be added. The new specification is as under:-

Sl. NO.	Labour with material (Lumpsum)		Total Amount
1)	<p>Providing and constructing toilet room (4' x 7' x 7' clear height) with double brick wall three sides and single brick wall front side with fiber glass door, plastering the walls from inside and outside, Aluminum Louver (25 mm thick) should be provided at one side on room, white glazed tiles (8" x 12") on flooring and on wall up to 3' height with fixing Indian type white glazed earthenware. Top of the toilet room is to be covered with Corrugated Asbestos Cement Sheet on 2" angle frame with 'J' bolts properly.</p> <p>White wash basin along with drain line is to be fitted inside the room 1/2" U PVC pipe water connection with brass tap to toilet & washbasin from nearest water pipe line as directed. Drainage line (4" PVC) from toilet to nearest chamber by cleaning, repairing & plastering the chamber by providing cement concrete top cover with M. S. frame.</p> <p>Providing and making brick steps at entrance & providing & applying white wash room from inside & outside.</p>	Lumpsum	
	TOTAL BASIC COST (Labour with material)		
	VAT TAX (% & Amount)		
	SERVICE TAX (% & Amount)		
	GRAND TOTAL (2+3+4)		

Note : Payment will be made as per Govt. prevailing Rules in case of GST implementation.

Signature and Seal of the party